LEGEND

Symbol	Meaning
	Survey Station
26.43	Level (cross indicates position unless arrowed)
	Kerb
	Drop Kerb
	Change of Surface
Top / Bottom	Banking
	Hedge / Bush Canopy
	Gate
	Wall
	Fence
	Foul Drainage (With dia. in mm)
	Storm Drainage (With dia. in mm)
OH	Overhead Electricity Line
UG	Underground Electricity Line
OH	Overhead Telephone Line
UG	Underground Telephone Line
0.8/9.0	Tree with Girth / Spread
	Sapling

ABBREVIATIONS (Where applicable)

GENERAL

Abbreviation	Meaning
AV.	Air Valve
BB.	Belisha Beacon
BG.	Box Gully
BL	Bollard
BP.	Boundary Post
BS.	Bus Stop
CD.	Cable Duct
CL.	Cover Level
CM.	Cable Marker
CPS.	Concrete Paving Slabs
DP	Down Pipe
ECB	Electricity Control Box
ECP.	Electricity Cable Pit
EJB.	Electricity Cable Junction Box
EP.	Electricity Pole
ERP.	Earthing Point
FB	Flower Bed
FH.	Fire Hydrant
FIG	Feeds into Ground
FP	Footpath
G.	Gully
GP.	Gate Post
GV.	Gas Valve
H	Hydrant
IC	Inspection Cover
IL	Invert Level
KO.	Kerb Outlet
LP	Lamp Post
MH	Manhole
MKR.	Marker
NB	Notice Board
NFI.	No Further Information
NSIF.	Not Surveyed – Information From
P	Post
PM	Parking Meter
PRV.	Pressure Reducing Valve
RE.	Rodding Eye
RG	Road Gully
RS	Road Sign
RWP.	Rain Water Pipe
SC.	Stop Cock
SP.	Signpost
SV.	Sluice Valve
T.	Tree
TCB.	Telephone Call Box
THL.	Threshold Level
TIC.	Telephone Inspection Cover
TJB.	Telephone Junction Box
TL.	Traffic Light
TP.	Telephone Pole
UTL.	Unable to Lift
VP.	Vent Pipe
WL.	Water Level
WM.	Water Meter
WV.	Water Valve

FENCES AND WALLS

Abbreviation	Meaning
BKW.	Brick Wall
BLW.	Block Wall
BW.	Post & Barbed Wire Fence
CB.	Close Boarded Fence
CI.	Corrugated Iron Fence
CP.	Chestnut Paling Fence
CW.	Concrete Wall
DSW.	Dry Stone Wall
IR.	Iron Railing Fence
OB.	Open Boarded Fence
PC.	Post & Chain Fence
PCL	Post & Chain Link Fence
PF.	Panel Fence
PR.	Post & Rail Fence
PW.	Post & Wire Fence
PWM.	Post & Wire Mesh Fence
RW.	Retaining Wall
SF.	Security Fence
STW.	Stone Wall
SW.	Sheep Wire Fence

OTHER ABBREVIATIONS USED ON THIS SURVEY

SURVEY STATION SCHEDULE

STN No	EASTINGS	NORTHINGS	REDUCED LEVEL
101	500.000	500.000	10.171
102	594.950	516.737	9.338
103	620.804	513.251	9.248
201	605.362	535.498	9.738
202	636.502	541.508	9.636
203	644.341	568.971	10.296
204	631.060	591.722	10.170
205	613.203	595.333	11.731
206	600.893	596.078	10.836
207	557.112	585.887	10.409
208	545.534	570.146	11.256
209	526.462	555.455	10.793
210	550.081	527.913	9.973
211	576.029	531.270	9.617
301	618.853	610.086	11.690
401	598.948	585.882	10.243
401	601.951	576.798	10.214
501	553.383	606.735	13.790
502	536.212	610.214	12.783
503	528.649	603.128	12.283
504	498.758	602.150	12.693
505	497.506	568.092	11.498